

Changi East Reclamation Project

Victor Choa

Nanyang Technological University, Singapore

ABSTRACT: This paper gives an overview of the Changi East Reclamation Project involving about 170 million m³ of sand fill for airport expansion and other infrastructural development. The project is underlain by deep deposits of soft marine clays and involves soil improvement using prefabricated vertical drains and surcharge. The sand fill is densified by dynamic compaction. The slope stability problems of the coastal protection rock bunds as well as the problems of capping a very soft silt pond of some 20 m deep of quarry waste shall be discussed. Comparisons are made between laboratory and in-situ testing methods to determine the properties of the marine clay. Lastly some preliminary results of a vertical drain pilot test are presented.

1 INTRODUCTION

The construction of Changi Airport in the late 1970s necessitated the reclamation of about 700 ha of land. The project involved dredging and hydraulic filling of 40 million m³ of sand by cutter suction dredgers. It was completed in 1979 (Choa, 1980). Changi Airport was completed in the early 1980s. In order to cater for future expansion of Changi Airport it is planned to reclaim a further 1500 ha of land using about 170 million m³ of sand. Due to the enormity of this undertaking it was decided to divide the next phase of reclamation into three sub-phases namely Changi East Reclamation Phase 1A, 1B and 1C. The overall Reclamation at Changi East is shown in Fig. 1.

The Reclamation Phase 1A commenced in January 1992 and is scheduled to be completed in January 1997. This phase was undertaken first in order to form a protective arm so that the subsequent phases of reclamation can be carried out in a relatively calm marine environment. It involves substantial coastal protection works in the form of rock bunds, headlands, sheet pile and pipe pile retaining walls.

The Reclamation Phase 1B which commenced about a year later in March 1993 is scheduled to complete in March 1988. This phase covers the

areas required for the future Runway 3 of Changi Airport and the associated taxiways and high speed turnoffs. It also covers the future terminal building and aircraft apron areas. Substantial soil improvement works is involved as the runway is underlain by deep deposits of soft marine clays. An enclosure of about 180 ha has been formed by sand dykes around a borrow pit where material was taken for reclamation of Changi Airport in the 1970s. This enclosure referred to as the "Silt Pond" had been filled by silt clay washings from sand quarrying operation. The up to 20 m thick layer of ultra soft silt and clay slurry within the "Silt Pond" shall be capped and improved under the Phase 1B reclamation project.

Reclamation Phase 1C is presently being designed and will probably commence sometime in 1996. This paper will deal mainly with the geotechnical problems associated with the first two phases of Changi East Reclamation Project.

2 SOIL CONDITION

Several geophysical surveys employing surface-towed boomer profiling systems were carried out. Soil borings with drilling rigs mounted on jack-up pontoons were also carried out prior to the

1006

Fig. 2 Reclamation Phase 1A





Fig. 1 Overall Site Plan



1008

The sheet pile lengths ranged from 12 to 26 m averaging 18 m. The box pile lengths ranged from 15 to 38 m averaging 24 m and the pipe pile lengths ranged from 15 to 40 m averaging 27 m. Wherever marine clay was encountered at the sheet pile retaining sections the soft clay was dredged out to a

layer with SPT 'N' values of greater than 50 blows. sheet piles were driven 3 m into the cemented sand box piles were installed at 4.2 m spacing. The 7,500 nos of sheet and box piles of 600 mm width and 1,600 nos of 610 mm diameter pipes piles. The 4.5 km long retaining walls comprised about

Fig. 5 Reclamation Phase 1B





Fig. 4 Sheet Pile Retaining Wall



An area of about 105 ha designated as Stage B shall be compacted by dynamic compaction. (Fig. 2). The compaction is required to densify the sand fill to a depth of 6 m to a density giving a cone penetration resistance of 10 MPa. The initial sand fill has a cone penetration resistance of between 4 to 10 MPa. The weight of hammer, height of drop, print spacing etc. is to be determined in a compaction trial. Work is expected to commence in April 1995. The area within 30 m behind the sheet pile wall is to be compacted by vibratory probes or other methods which will not damage the retaining system. Trials will also be carried to determine the method of compaction. The degree and extent of densification is similar to the dynamic compaction areas.

Stability in this project is complicated by the existence of telecommunication submarine cables laid in shallow trenches underlying the reclamation (Fig. 2). A staged construction was required over these cables. A build-up of sand fill by 0.5 m layers with rest periods between lifts was specified for filling over a width of 50 m on either side of the cable. A trial reclamation section was carried out using inclinometers and settlement gauges to monitor the movements as each stage was built up with suitable rest periods. Work was allowed to commence over the cable itself only after the satisfactory completion of the trial reclamation in soil conditions similar to those that underlie the cables.


3.2 Staged construction

depth of 5 to 6 m and backfilled with sand to form a sand and key. All the landside pipe piles were flushed out and ground anchors with 1,000 kN working load were installed below the toe of these piles. Inclinometers were installed in the sheet pile walls to monitor the movements during the backfilling of the wall.

3.3 Sand compaction

The reclamation over these cables has been successfully executed and the placement of the rock protection works are in progress.

Fig. 6 Soil Profile and Properties



The soft marine clays underlying the runway, taxiways and turnout areas occur to depths of about 40 to 50 m below the seabed. Prefabricated band drains of about 100 mm width are to be installed at square grids of 1.5 m and 1.7 m under the runway and taxiway/turnoffs respectively. The height of

4.1 Vertical drains and surcharge


The surcharge level is reduced to +5.0 mCD and the sand over the runway and taxiways/turnoffs is densified by dynamic compaction. The final level of the reclamation is to be between +5.0 and +5.5 mCD. Additionally a 3.8 km long containment sand bund with a top width of 30 m is constructed to provide a spill over area for the capping of the "Silt Pond" with sand to a level of +4.0 mCD. The proposed method of filling is to spread the sand in thin layers not exceeding 10 cm per pass and for each lift to be between 0.5 to 1.0 m thick. About one to two weeks rest periods between each lift is to be provided for the underlying soil to gain sufficient strength to support the subsequent filling. Vertical drains are to be installed at +4 mCD and sand surcharge is to be placed initially to +7.5 mCD and finally to +9.0 mCD in order to improve the very soft silt and clay slurry.

The seabed is generally between -3 mCD to -5 mCD and the reclamation is initially brought to +4 mCD. At this platform level prefabricated band-shaped vertical drain are installed over the runway, taxiways and high speed turnout areas. Surcharge is then placed hydraulically to +10.0 mCD and +8.5 mCD over the runway and taxiways/turnoffs respectively. After a surcharge period of 18 months

equipment was deployed to boost the reclamation production rate. At peak a fleet of additional dredging bottom opening barges of 2,000 to 4,000 m² transportation of sand was also supplemented by the sand from the borrow source. The dredger of 3,000 m³ capacity were also used to win of 1,200 HP capacity as well as a suction hopper capacities of 8,000 HP to 20,000 HP. Sand pumps the reclamation site by cutter suction dredgers with repumped through 600 mm diameter pipe lines to rehandling pits adjacent to the reclamation site and capacity respectively. The sand is deposited into propelled hopper barges of 9,000 m³ and 3,000 m³ away by trailing suction hopper dredgers and self transported from borrow sources about 30 to 45 km million m³ of sand. (Fig. 5). The sand is transported from borrow sources about 30 to 45 km

4 RECLAMATION PHASE 1B

Fig. 7 Soil Properties at FT-4



The entire sand fill under the runway, taxiways, and turnoffs are to be densified. The seabed is approximately at -3 mCD to -5 mCD and the densification is to be carried out from +5 mCD. The proposed method of compaction is by the dynamic compaction method comprising of tamping the ground with drop weights. The compaction rigs are to be capable of imparting a minimum energy of 500 t-m (ton-metre) per blow (or such higher capacity rigs if the Contractor so desires). A total compactive effort (impact energy) of at least 300 t-m/m² and 400 t-m/m² is required in the areas requiring 12 MPa and 15 MPa cone penetration resistance respectively. The Contractor will be required to impart the above specified densities. If however, the above total compactive effort is insufficient to achieve the specified densities as determined by the cone penetration test and other tests then the Contractor is required at no

Colbond prefabricated band shaped drains are currently being installed by nine drain stitchers using static or vibratory force to advance the handrel. The maximum depth of penetration of the handrels range from 24 to 50 m. The current rate of installation is between 3,000 to 8,000 m per rig per 10 hour working day. The average rate is about 1,000 m per rig per day. A total of 19 million metres of drains are to installed.

The very soft silts and clays in the "Silt Pond" are also to be improved with vertical drains at 2.0 m square grid. The surface of the very soft silts and clays are at -4 mCD and thickness is up to 20 m. A surcharge of up to +9.0 mCD will be placed after drain installation at +4.0 mCD. There is a possibility that the first round of drain installation may fail to produce the desired improvement due to the large strain envisaged as well as the very fine nature of some of the mine washings. In this event a contingency of a second round of supplemental drain installation at 2.0 m square is allowed for.

4.2 Sand compaction

A strict quality control of the drains is in place where samples are taken daily for laboratory testing. The frequency of sampling is one per 20,000 m of drains installed. Tensile strength, filter permeability and discharge capacity of the drains are some of the tests being routinely carried out.

surcharge is 6 m and 4.5 m for the runway and taxiway/turnoffs respectively. A degree of consolidation of 90% is specified throughout the entire depth of the compressible layer overlying the cemented sand layer. A minimum surcharge period of 18 months has also been specified.

Fig. 8 Coefficient of Consolidation at FT-4




Fig. 10 Lateral Earth Pressure Measurements





Fig. 9 Comparison of Undrained Shear Strength from In-situ and Laboratory Tests



additional cost to the Client to impart such specified densities. The method of compaction such as powder weight, height of drop, number of drops per location, spacing of pounding locations, number of compaction phases are to be determined in a compaction trial prior to the commencement of the main compaction works.

The acceptance criterion are to be determined by Cone Penetration Tests, Pressurimeter Tests, Standard Penetration Tests and surface settlements. The minimum cone penetration resistance after compaction is to be 12 MPa and 15 MPa under the taxiway/runoffs and runway respectively. The equivalent acceptance criteria for pressurimeter tests is to be limit pressures of 1.5 and 2.0 MPa and pressurimeter moduli of 20 and 25 MPa. The equivalent Standard Penetration Tests is to be corrected 'N' values which indicate 65% and 73% Relative Density respectively. The settlement criteria is to be established during the compaction trial.

With the use of vertical drains, the horizontal coefficient of consolidation C_h becomes one of the most important consolidation parameters. In-situ tests, such as SBPM holding tests, cone penetrometer (CPTu) dissipation tests, as well as flat dilatometer (FDM) tests, were used to measure

7(b). The permeability of soil can also be determined indirectly by oedometer tests, as shown in Fig. 7(c). The permeability of soil was also measured by BAT permeameter tests as well as indirectly determined by self-bored pressurimeter (SBPM) tests and the results are also presented in Fig. 7(c). It should be noted that the SBPM test measures the horizontal permeability. Nevertheless, the distributions of permeability with depth measured by the three different methods are quite close.


ie preconsolidation pressure p_c , the compression index C_c and the vertical coefficient of consolidation C_v were determined by conventional oedometer tests (with 24 hour loading for each test). The distribution of these parameters with the depth below seabed are presented in Figs. 7(a) and

1 Consolidation behaviour

extensive in-situ and laboratory tests were conducted to investigate the consolidation and shear length properties of marine clay. For illustrative purposes, only the soil properties measured for section FT-4 are discussed in the following. The mineral soil profile at FT-4 is shown in Fig. 6.

PROPERTIES OF THE MARINE CLAY

Fig. 11 Vertical Drains Pilot Test



LEGEND



- ▲ VS WATER STAND PIPE
- PP PNEUMATIC PRESSUREMETER
- SP SURFACE SETTLEMENT PLATE
- DS DEEP SETTLEMENT GAUGE
- ▲ MS MULTI LEVEL SETTLEMENT DEVICE
- * SG SETTLEMENT GAUGE
- ◆ IN INCLINOMETER

were also performed to measure the C_p values of soils. Generally the C_p values measured for the overconsolidation region was found to be much greater than the C_v values measured by the conventional oedometer tests. The C_p profiles measured by the laboratory and in-situ tests over the normally consolidated range are compared in Figs. 8(b) and 8(c). For the FDM and CPTu tests, the converted values are used for plotting Figs. 8(b) and 8(c). It can be seen that although the C_p values measured by the FDM tests for the upper marine clay are still much larger, the C_p measured by the CPTu tests show a good agreement with the laboratory measurements. The C_p values measured are generally a number of times larger than the C_v values.

The C_p values of the soil. The distribution curves of C_p versus depth measured by these three methods are presented in Fig. 8(a). It can be seen that although the measurements by FDM and CPTu tests are relatively close, the values measured by the SBPM tests can be many times larger. It should be pointed out that the C_p values measured by the above three methods are more relevant to the recompression index. Different correction methods have been suggested to convert the measured value to the C_p value for the normally consolidated region. Furthermore, the methods are not yet well established and there are various uncertainties involved in each of the tests.

Laboratory tests with a 75 mm diameter Rowe cell and a 76 mm diameter hydraulic consolidometer

Fig. 12 Drains at 1.5 x 1.5 m square grid





of FV tests, but is much lower than that of SBPM and FDM tests. The difference may be due to the sample disturbances. However, considering the fact that a CK_0U test consolidates the specimen to more or less the same in-situ stress state before shearing, the sample disturbances should be abated to some extent. The difference in the stress condition and the failure mode may be one of the main reasons. A SBPM or a FDM test imposes a plane strain condition while a triaxial test an axisymmetric condition. Past studies with true triaxial and plane strain cells have established that the shear strength determined for a plane strain condition can be quite different from that for an axisymmetric condition. This factor therefore should be taken into account in the analysis.

to measure the undrained shear strength of marine clay, different triaxial tests as well as direct simple shear tests were performed. The triaxial tests include unconsolidated undrained (UU) tests, isotropic consolidated undrained compression (IUC) tests, K_0 consolidated and undrained compression (CK_0UC) tests, and constant axial stress ($\sigma'_v = \text{const.}$) tests.

in-situ tests, such as the field vane (FV) tests, the FDM tests, and the SBPM tests were also used to measure the undrained shear strength of clay. A comparison of the different in-situ tests with the laboratory tests is presented in Fig. 9. It can be seen at the test data of CK_0U tests coincides with that

2 The undrained shear strength measurement

Fig. 13 Drains at 1.7 x 1.7 m square grid





The use of SBPM has enabled the in-situ lateral stress to be measured. The total and effective in-situ lateral stresses measured by SBPM tests at FT-4 are plotted in Fig. 10(a) together with the in-situ vertical effective stress. Triaxial K_0 consolidation tests with the control of zero lateral strain of the specimen were also used to measure the K_0 values. The K_0 values estimated by both methods are compared in Fig. 10(b). It can be seen that the K_0 values measured by SBPM tests appear to be extremely high compared to the laboratory K_0 values.

5.3 In-situ lateral stress measurement

The consistently higher measurements by the SBPM tests than by the FDM tests for both the consolidation parameters (Fig. 8a) and undrained shear strength probably indicate that the stiffness of the soil may have been over-estimated. This speculation is supported by the lateral stress measurements presented in the next section. Some further laboratory testing with a new plane strain cell and with a torsional hollow cylinder machine have been planned to verify the measurements made by SBPM tests.

The UU tests, on the other hand, considerably underestimate the undrained shear strength of soil, as reported by many others.

Fig. 14 No Drain Area



over 1.25 m has been placed over the very soft silts and clays. There is every indication that the "Silt Pond" can be successfully capped by the proposed sand spreading method.

ACKNOWLEDGMENT

The assistance and co-operation of SPSCS Consultants Pte Ltd, Singapore, Dr Chu Jian and Mr Bo Myint Win are gratefully acknowledged.

REFERENCES

- Choa, V. 1980. Geotechnical aspects of a hydraulic fill reclamation project. Proc. 6th SE Asian Conf. Soil Engng, Taipei 1, 469-484.
- Choa, V. 1994. Application of the observational method to hydraulic fill reclamation projects. Geotechnique 44, No 4, 735-745.

A pilot test is being carried out to study the drain at square grid spacings of 1.5 m, 1.7 m and 2.0 m. A control zone without drains was also designated. Fig. 11 shows the plan and section of the pilot test area which is situated just beyond the north east corner of the 'Silt Pond'. Soil instrumentation are also shown on Fig. 11. The results of the 1.5 m, 1.7 m and no drain areas are shown in Figs. 12, 13 and 14. The preliminary back analyses of the pilot test results after only about one year since the vertical drain installation and placement of the surcharge indicate that between 70% to 80% of consolidation has taken place in all three drain ones. The back analyses are based on settlement measurements and on the ultimate settlements predicted by Asakaka's method, the hyperbolic method and on conventional one dimensional consolidation analyses using laboratory test results. Generally the lowest degree of consolidation was obtained based on the laboratory results. The degree of consolidation in the no drain area is estimated to be around 25%. As expected the pore pressure measurements were very difficult to interpret.

CONCLUSION

Both the reclamation projects Phase 1A and Phase 3 are progressing extremely well. The sub-division of the reclamation into the sub-phases of approximately equal size and the timing of the reclamation has therefore proven to be a reasonably good decision.

The observational method used for controlling the staged construction of the reclamation and coastal defence works has been very successful with no failures encountered.

A pilot test for the prefabricated vertical drains indicate that the choice of the 1.5 m and 1.7 m rare grid spacing for the treatment of the way, taxiways and turnoffs is adequate.

The "Silt Pond" is currently being capped by leading sand in small lifts approximately 10 to 15 cm per pass with suitable rest periods after several passes. Preliminary indications is that the sand loss is less than 30% including some settlement. As at February 1995 a net thickness